ज्ञान शांति मैत्री

आज़ादी का अमृत महोत्सव

Mahatma Gandhi Antarrashtriya Hindi Vishwavidyalaya, Wardha
Gandhi Hill, Wardha- 442001. (Maharashtra)
[Phone No. 07152 – 232669]
[Website : www.hindivishwa.org]

Tender No. MGAHV/CD/34/2023-24/.05 **Date : 26 /05/2023**

Tender Notice

Sealed tenders are invited for Construction of CC road & Leveling work near Haldi Ghati & Providing and Fixing of Paver block in Chhatrapati Sambhaji Maharaj Hostel at North Campus MGAHV, Wardha. The tender should reach the University on or before 26/06/2023 up to 04:00 p.m.

The detailed terms and conditions of tender can be obtained from **www.hindivishwa.org** and **www.eprocure.gov.in**

कादर नवाज़
Registrar
26/05/23

ज्ञान शांति मैत्री

आज़ादी का अमृत महोत्सव

MAHATMA GANDHI ANTARRASHTRIYA HINDI VISHWAVIDYALAYA

Post Hindi Vishwavidyalaya, Gandhi Hills, Wardha-442 001.
(Phone 07152-232669 Fax No 07152-247602)
[Website : www.hindivishwa.org]

Tender No. : MGAHV/CD/34/2023-24/05 **Date : 26.05.2023**

TENDER FOR

Construction of CC road & Leveling work near Haldi Ghati & Providing and Fixing of Paver block in Chhatrapati Sambhaji Maharaj Hostel at North Campus MGAHV, Wardha.

TENDER FORM SALE WILL START FROM	:	10.00 AM on 29.05.2023
LAST DATE FOR SALE OF TENDER FORM	:	Upto 03.00 PM on 26.06.2023
LAST DATE FOR SUBMISSION OF TENDER FORM	:	Upto 4.00 PM on 26.06.2023
DATE OF OPENING OF TENDER (i.e. Technical Bid)	:	At 03.00 PM on 27.06.2023

- **Tender available on www.eprocure.gov.in & www.hindivishwa.org**

TENDER FORM PRICE Rs. 500/-

निविदाकर्ता द्वारा भरे जाने वाली जानकारी

क्र. सं.	विवरण		निविदाकर्ता द्वारा भरे जाने वाला विवरण	संलग्नक क्रमांक
1.	फर्म का नाम एवं पता	:		
2.	फर्म के Proprietor/Partner का नाम	:		
3.	मोबाइल नम्बर	:		
4.	ईमेल आईडी	:		
5.	फर्म का पंजीकरण क्रमांक व तिथि	:		
6.	पंजीकृत करने वाले विभाग का नाम	:		
7.	जी.एस.टी. नम्बर	:		
8.	पैन नम्बर	:		
9.	आधार क्रमांक	:		
10.	अनुभव प्रमाण पत्र	:		
11.	विगत क्रमिक तीन वर्षो का आयकर रिटर्न प्रमाण पत्र	:		
12.	श्रमिक का बीमा प्रमाण पत्र	:		
13.	UNDERTAKING REGARDING NOT BEING BLACKLISTING	:		
14.	संलग्न डी.डी. का विवरण	:	राशि रू. .... दिनांक .... बैंक का नाम .... शाखा	
14.	अन्य प्रमाण पत्र	:		

महात्मा गांधी अंतरराष्ट्रीय हिंदी विश्वविद्यालय, वर्धा

(संसद द्वारा पारित अधिनियम के अन्तर्गत स्थापित केन्द्रीय विश्वविद्यालय)

पोस्ट-हिंदी विश्वविद्यालय, गांधी हिल्स, वर्धा - 442001 (महाराष्ट्र),

(फोन-07152-232669 फैक्स-07152-247602)

वेबसाइट :www.hindivishwa.org

Name of work **Construction of CC road & Leveling work near Haldi Ghati & Providing and Fixing of Paver block in Chhatrapati Sambhaji Maharaj Hostel at North Campus MGAHV, Wardha.**

Tender No. : MGAHV/CD/34/2023-24/.05 **Date : 26.05.2023**

(Technical Bid and other conditions)

1- कार्य का विवरण – संलग्न

2- EMD राशि रु. 10000/- **मांगपत्र– वित्ताधिकारी म.गां.अं.हिं.वि..वर्धा. महाराष्ट के नाम देय**

3. जी.एस.टी. क्रमांक अनिवार्य। (छायाप्रति संलग्न करना अनिवार्य)

4. PAN क्रमांक अनिवार्य। (छायाप्रति संलग्न करना अनिवार्य)

5. विगत क्रमिक तीन वर्षो (2019-20, 2020-21, 2021-22) का वर्षवार केन्द्र सरकार एवं राज्य सरकार के अनुदानित संस्थानों में सिविल कार्य कराने का अनुभव प्रमाण पत्र जमा करना अनिवार्य होगा। जो कि प्रत्येक वित्तीय वर्ष में रूपया 15 लाख से कम न हो।

6. Technical & Financial bid को अलग-अलग लिफाफों में सीलबंद कर एक बड़े लिफाफे में डालकर लिफाफा बंद करना होगा और उस लिफाफे पर 'Construction of CC road & Leveling work near Haldi Ghati & Providing and Fixing of Paver block in Chhatrapati Sambhaji Maharaj Hostel at North Campus MGAHV, Wardha' लिखकर जमा करना अनिवार्य होगा।

7. निविदा भरने से पूर्व कार्यस्थल का निरीक्षण करना अपेक्षित है। किसी भी प्रकार की जानकारी/स्पष्टीकरण परिसर विकास विभाग कार्यालय से कार्य दिवसों/कार्य समयों में प्राप्त की जा सकती है।

8. निविदा में दी गई दरें 06 (छः) माह तक वैध रहेंगी।

9. कार्यादेश जारी होने के पश्चात 60 दिनों में कार्य पूर्ण करना होगा। विलम्ब की दशा में प्रतिदिन रु. 1,000/- दण्ड स्वरूप बिल से कटौती की जाएगी।

10. उक्त निविदा में संपूर्ण सामग्री, श्रमिक व्यय एवं कर आदि सम्मिलित करना होगा।

11. निविदाकारक को विगत क्रमिक तीन वर्षो (2019-20, 2020-21, 2021-22) का आयकर रिटर्न प्रमाण पत्र जमा करना अनिवार्य होगा।

12. श्रमिकों का बीमा होना अनिवार्य। (कार्यादेश प्राप्ति के बाद परिसर विकास विभाग में प्रमाण पत्र प्रस्तुत करने के बाद ही कार्य प्रारम्भ करना होगा)

13. कोरोना वायरस के फैलाव को रोकने हेतु सामाजिक दूरी (Social Distance) बनाए रखने एवं सरकारी दिशानिर्देशों का पालन करते हुए निविदाकारक एवं श्रमिकों द्वारा कार्य का निष्पादन किया जाएगा।

14. कार्य के दौरान यदि किसी प्रकार की दुर्घटना घटित होती है तो उसकी संपूर्ण जिम्मेदारी निविदाकारक की होगी।

15. कार्यादेश प्राप्त निविदाकर्ता को भारत सरकार/महाराष्ट्र सरकार के श्रम कानूनों, बाल मजदूरी कानूनों आदि नियमों का पालन करना अनिवार्य होगा।

16. कार्यादेश प्राप्त निविदाकर्ता को कार्यों की गुणवत्ता सुनिश्चित करने संबंधी केंद्रीय लोक निर्माण विभाग की विशिष्टियों के अनुरुप कार्य सम्पादित करना होगा तथा बिल के साथ आवश्यक टेस्ट रिपोर्ट जमा किया जाना होगा।

17. कार्य के दौरान होने वाली किसी भी प्रकार की क्षति के लिए विश्वविद्यालय का उत्तरदायित्व अथवा देनदारी नहीं होगी और न ही इस प्रकार का कोई दावा न तो कार्यादेश प्राप्त निविदाकर्ता द्वारा और न श्रमिकों द्वारा किया जायेगा और न ही विश्वविद्यालय द्वारा स्वीकार किया जायेगा।

18. वित्तीय निविदा में विभिन्न आइटमों की दर्शायी गयी मात्रा अनुमानित है। कार्य सम्पादन के समय किसी भी आइटम की मात्रा में संशोधन हो सकता है या कोई कार्य नहीं भी सम्पादित कराये जाने का निर्णय लिया जा सकता है। उक्त हेतु कार्यादेश प्राप्त निविदाकर्ता का कोई दावा स्वीकार नहीं होगा।

19. कार्य के दौरान यदि विश्वविद्यालय की बिजली का उपयोग किया जाता है तो प्रति यूनिट रु. 10.00 के अनुसार कार्यादेश प्राप्त निविदाकर्ता को विश्वविद्यालय के पक्ष में भुगतान करना होगा। कार्यादेश प्राप्त निविदाकर्ता द्वारा बिजली मीटर का व्यय स्वयं वहन करना होगा तथा विभाग के इलेक्ट्रीशियन के माध्यम से ही बिजली कनेक्शन लेना होगा।

20. निविदा प्रपत्र एवं संलग्न दस्तावेज़ के प्रत्येक पृष्ठ पर निविदाकारक द्वारा हस्ताक्षर एवं मुहर लगाना अनिवार्य है।

21. वित्तीय निविदा में दरों का अधिलेखन (Overwriting) मान्य नहीं होगा इसलिए वित्तीय निविदा में दरों को बहुत ही ध्यान से और बिना अधिलेखन (Overwriting) के भरा जाए।

22. वित्तीय निविदा में त्रुटिपूर्ण गणना (Wrong Calculation) मान्य नहीं होंगी। किसी भी प्रकार के संदेह की स्थिति में शब्दों में लिखी गई राशि ही मान्य होगी।

23. निविदा को कुलसचिव कार्यालय में रखे Tender Box में डालना होगा।

24. सभी अर्हताएँ निविदा जमा करने से पूर्व या अंतिम तिथि तक पूर्ण करना अनिवार्य है।

25. कार्य पूर्ण होने के उपरान्त विश्वविद्यालय के अभियंताओं एवं परामर्शदाता द्वारा कार्य के सत्यापन एवं बिल की जाँच के उपरांत ही भुगतान की कार्यवाही संपन्न की जाएगी।

26. निविदा प्रपत्र प्राप्त करने हेतु **'वित्ताधिकारी, म.गां.अं.हिं.वि., वर्धा (महाराष्ट्र)'** के नाम से देय रु. 500/- (रु. पांच सौ मात्र) का डिमांड ड्राफ्ट परिसर विकास विभाग में जमा कर निविदा प्रपत्र प्राप्त किया जा

सकता है। यदि निविदाकारक द्वारा वेबसाइट से निविदा प्रपत्र डाउनलोड कर निविदा जमा की जाती है तो उक्त निविदा प्रपत्र के साथ **'वित्ताधिकारी, म.गां.अं.हिं.वि., वर्धा (महाराष्ट्र)'** के नाम से देय रू. 500/- का डिमांड ड्राफ्ट जोड़ना अनिवार्य है।

27. निविदा प्राप्त करने वाली फर्म को कार्यादेश जारी होने के 05 दिनों के अंदर निविदा की लागत का 05% Performance Security के रूप में 06 माह के लिए धनराशि डी.डी. के माध्यम से **'वित्ताधिकारी, म.गां. अं.हिं.वि., वर्धा (महाराष्ट्र)'** के नाम से विश्वविद्यालय में जमा करना अनिवार्य होगा।

28. तकनीकी निविदा में सफल निविदाकारक को ई-मेल/दूरभाष के माध्यम से सूचित किया जाएगा जिससे तकनीकी निविदा में सफल समस्त निविदाकारक 'वित्तीय निविदा' खुलने के समय उपस्थित रह सकें। अतः लिफाफे के ऊपर ईमेल, मोबाइल नम्बर एवं पता अवश्य लिखें।

29. निविदा में किसी भी प्रकार के परिवर्तन/सुधार/संशोधन होने पर उक्त की सूचना मात्र विश्वविद्यालय की वेबसाइट www.hindivishwa.org पर प्रकाशित की जाएगी इसलिए वेबसाइट लगातार देखते रहें।

30. विश्वविद्यालय के पास किसी भी स्तर पर निविदा में निर्धारित जानकारी, शर्तों, प्रक्रिया और प्रोटोकॉल को रद्द करने और जोड़ने का विवेकाधिकार सुरक्षित होगा। इसके खिलाफ निविदाकर्ता का कोई भी दावा स्वीकार्य नहीं होगा।

31. विश्वविद्यालय बिना कोई कारण बताये किसी भी समय निविदा को निरस्त करने का अधिकार अपने पास सुरक्षित रखता है। किसी भी विवाद की दशा में विवादों का क्षेत्राधिकार वर्धा (महाराष्ट्र) ही होगा।

टेंडर भरने वाले का हस्ताक्षर एवं मुहर

UNDERTAKING REGARDING NOT BEING BLACKLISTING

It is hereby certified that, I/we ____ are not blacklisted by any Ministry/ Departments of Central/ State Government, International bodies like United Nations, World Bank or any other organization/ Funding Agencies as on date. The Organization will immediately inform to M.G.A.H.V, Wardha in case of any change in the situation any time here in after.

Place: ___________
Date: __/___/____

Name:_______________________

Designation__________________

Seal

(Financial Bid)

Tender No. : MGAHV/CD/34/2023-24/05 **Date : 26.05.2023**

(Part-A)

Construction of CC road & Leveling work near Haldi Ghati at North Campus MGAHV, Wardha.

S.NO	Description	Unit	Qty.	Rate	Total Amount (In figure)	Total Amount (In words)
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth. 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m, disposed earth to be levelled and neatly dressed					
	All kinds of soil					
	Near Haldi Ghati	cum	302.40			
2	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level :					
	1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size).					
	Near Haldi Ghati	cum	9.30			
3	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m	cum	240.00			

S.NO	Description	Unit	Qty.	Rate	Total Amount (In figure)	Total Amount (In words)
4	Providing and laying design mix cement concrete of M-30 grade, in roads/ taxi tracks/ runways, using cement content as per design mix, using coarse sand and graded stone aggregate of 40 mm nominal size in appropriate proportions as per approved & specified design criteria, providing dowel bars with sleeve/ tie bars wherever required, laying at site, spreading and compacting mechanically by using needle and surface vibrators, levelling to required slope/ camber, finishing with required texture, including steel form work with sturdy M.S. channel sections, curing, making provision for contraction/ expansion, construction & longitudinal joints (10 mm wide x 50 mm deep) by groove cutting machine, providing and filling joints with approved joint filler and sealants, complete all as per direction of Engineerin-charge (Item of joint fillers, sealants, dowel bars with sleeve/ tie bars to be paid separately).					
	Cement concrete prepared with batch mixing machine	cum	10.32			
5	Centering and shuttering including strutting, propping etc. and removal of form for :					
	Foundations, footings, bases of columns, etc. for mass concrete	sqm	5.20			
	Total (A)					

Tender No. MGAHV/CD/34/2023-24/05 Date: 26.05.2023

(Part-B)

Name of work - Providing and fixing of Paver block and drain cover with Kota stone at Chhatrapati Sambhaji Maharaj Hostel

S.NO	Description	Unit	Qty.	Rate	Total Amount (In figure)	Total Amount (In words)
1	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead upto 50 m and lift upto 1.5 m.					
	All kinds of soil **(425.4cum / 100= 8.25)**	Sqm	4.25			
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth. 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m, disposed earth to be levelled and neatly dressed					
	All kinds of soil	Cum	180.00			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level :					
	1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size).	cum	5.60			
4	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m	cum	180.00			
5	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) :					
	25 mm thick	Sqm	16.80			

S.NO	Description	Unit	Qty.	Rate	Total Amount (In figure)	Total Amount (In words)
6	Providing and laying factory made coloured chamfered edge Cement Concrete paver blocks of required strength, thickness & size/shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of fine sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with jamuna sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand in footpath, parks, lawns, drive ways or light traffic parking etc. complete as per manufacturer's specifications & direction of Engineer-in-Charge. 60mm thick C.C. paver block of M-35 grade with approved colour, design & pattern.	Sqm	56.00			
7	Providing and laying design mix cement concrete of M-30 grade, in roads/ taxi tracks/ runways, using cement content as per design mix, using coarse sand and graded stone aggregate of 40 mm nominal size in appropriate proportions as per approved & specified design criteria, providing dowel bars with sleeve/ tie bars wherever required, laying at site, spreading and compacting mechanically by using needle and surface vibrators, levelling to required slope/ camber, finishing with required texture, including steel form work with sturdy M.S. channel sections, curing, making provision for contraction/ expansion, construction & longitudinal joints (10 mm wide x 50 mm deep) by groove cutting machine, providing and filling joints with approved joint filler and sealants, complete all as per direction of Engineerin-charge (Item of joint fillers, sealants, dowel bars with sleeve/ tie bars to be paid separately).					
	Cement concrete prepared with batch mixing machine	cum	13.95			
	Total (B)					
	Total (A+B)					
	GST @					
	GRAND TOTAL					

टेंडर भरने वाले का हस्ताक्षर एवं मुहर