



Mahatma Gandhi Antarrashtriya Hindi Vishwavidyalaya, Wardha

Gandhi Hill, Wardha- 442001. (Maharashtra)

[Phone No. 07152-230902]

[Website : www.hindivishwa.org]

Tender No. MGAHV/CD/34/2023-24/.12

Date : 08 / 08 /2023

Tender Notice

Sealed tenders are invited Construction of Parking shed infront of Dining and Kitchen (North Campus) at MGAHV, Wardha. The tender should reach the University on or before 31/08/2023 up to 04:00 p.m.

The detailed terms and conditions of tender can be obtained from www.hindivishwa.org and www.eprocure.gov.in

कादर नवाज
Registrar 08/08/23



MAHATMA GANDHI ANTARRASHTRIYA HINDI VISHWAVIDYALAYA

Post Hindi Vishwavidyalaya, Gandhi Hills, Wardha-442 001.

(Phone 07152-230902)

[Website : www.hindivishwa.org]

Tender No. : MGAHV/CD/34/2023-24/..12..

Date : 08.08.2023

TENDER FOR **Civil & Fabrication work**

TENDER FORM SALE WILL START FROM	:	10.00 AM on 09.08.2023
LAST DATE FOR SALE OF TENDER FORM	:	Upto 03.00 PM on 31.08.2023
LAST DATE FOR SUBMISSION OF TENDER FORM	:	Upto 4.00 PM on 31.08.2023
DATE OF OPENING OF TENDER (i.e. Technical Bid)	:	At 05.00 PM on 31.08.2023

- Tender available on www.eprocure.gov.in & www.hindivishwa.org

TENDER FORM PRICE Rs. 500/-

निविदाकर्ता द्वारा भरी जाने वाली जानकारी

क्र. सं.	विवरण		निविदाकर्ता द्वारा भरे जाने वाला विवरण	संलग्नक क्रमांक
1.	फर्म का नाम एवं पता	:		
2.	फर्म के Proprietor/Partner का नाम	:		
3.	मोबाइल नम्बर	:		
4.	ईमेल आईडी	:		
5.	फर्म का पंजीकरण क्रमांक व तिथि	:		
6.	पंजीयन करने वाले विभाग का नाम	:		
7.	जी.एस.टी. नम्बर	:		
8.	पैन नम्बर	:		
9.	आधार क्रमांक	:		
10.	अनुभव प्रमाण पत्र	:		
11.	विगत क्रमिक तीन वर्षों का आयकर रिटर्न प्रमाण पत्र	:		
12.	श्रमिक का बीमा प्रमाण पत्र	:		
13.	UNDERTAKING REGARDING NOT BEING BLACKLISTING	:		
14.	संलग्न डी.डी. का विवरण	:	राशि ₹ दिनांक बैंक का नाम शाखा	
14.	अन्य प्रमाण पत्र	:		

निविदा भरने वाले का हस्ताक्षर एवं मुहर



महात्मा गांधी अंतरराष्ट्रीय हिंदी विश्वविद्यालय, वर्धा

(संसद द्वारा पारित अधिनियम के अन्तर्गत स्थापित केन्द्रीय विश्वविद्यालय)
पोस्ट-हिंदी विश्वविद्यालय, गांधी हिल्स, वर्धा - 442001 (महाराष्ट्र),
(फोन-07152-230902)

वेबसाइट : www.hindivishwa.org

Name of work : Construction of Parking shed in front of Dining and Kitchen
(North Campus) at MGAHV, Wardha.

Tender No. : MGAHV/CD/34/2023-24/ 12...

Date : 08.08.2023

(Technical Bid and other conditions)

- 1- कार्य का विवरण - संलग्न
- 2- EMD राशि ₹ 43000/-
3. जी.एस.टी. क्रमांक अनिवार्य। (छयाप्रति संलग्न करना अनिवार्य)
4. PAN क्रमांक अनिवार्य। (छयाप्रति संलग्न करना अनिवार्य)
5. विगत क्रमिक तीन वर्षों (2020-21, 2021-22, 2022-23) का केन्द्र सरकार एवं राज्य सरकार के अनुदानित संस्थानों में सिविल व फ़ैब्रीकेशन कार्य कराने का अनुभव प्रमाण पत्र जो कि प्रत्येक वित्तीय वर्ष में रुपया चालीस लाख से कम न हो को सनदी लेखाकार (Chartered Accountant) से प्रमाणित कर जमा करना अनिवार्य होगा।
6. Technical & Financial bid को अलग-अलग लिफाफों में सीलबंद कर एक बड़े लिफाफे में डालकर लिफाफा बंद करना होगा और उस लिफाफे पर 'Construction of Parking shed in front of Dining and Kitchen (North Campus) at MGAHV, Wardha..' लिखकर जमा करना अनिवार्य होगा।
7. निविदा भरने से पूर्व कार्यस्थल का निरीक्षण करना अपेक्षित है। किसी भी प्रकार की जानकारी/स्पष्टीकरण परिसर विकास विभाग कार्यालय से कार्य दिवसों/कार्य समयों में प्राप्त की जा सकती है।
8. निविदा में दी गई दरें 06 (छः) माह तक वैध रहेंगी।
9. कायदेशि जारी होने के पश्चात 75 दिनों में कार्य पूर्ण करना होगा। विलम्ब की दशा में प्रतिदिन ₹ 1,000/- दण्ड स्वरूप बिल से कटौती की जाएगी।
10. उक्त निविदा में संपूर्ण सामग्री, श्रमिक व्यय एवं कर आदि सम्मिलित करना होगा।
11. निविदाकार को विगत क्रमिक तीन वर्षों (2020-21, 2021-22, 2022-23) का आयकर रिटर्न का प्रमाण पत्र सनदी लेखाकार (Chartered Accountant) से प्रमाणित कर जमा करना अनिवार्य होगा।
12. श्रमिकों का बीमा होना अनिवार्य। (कायदेशि प्राप्ति के बाद परिसर विकास विभाग में संबंधित प्रमाण पत्र प्रस्तुत करने के बाद ही कार्य प्रारम्भ करना होगा)

13. कोरोना वायरस के फैलाव को रोकने हेतु सामाजिक दूरी (Social Distance) बनाए रखने एवं सरकारी दिशानिर्देशों का पालन करते हुए निविदाकारक एवं श्रमिकों द्वारा कार्य का निष्पादन किया जाएगा।
14. कार्य के दौरान यदि किसी प्रकार की दुर्घटना होती है तो उसकी संपूर्ण जिम्मेदारी निविदाकारक की होगी।
15. कायदेश प्राप्त निविदाकर्ता को भारत सरकार/महाराष्ट्र सरकार के श्रम कानूनों, बाल मजदूरी कानूनों आदि नियमों का पालन करना अनिवार्य होगा।
16. कायदेश प्राप्त निविदाकर्ता को कार्यों की गुणवत्ता सुनिश्चित करने संबंधी केंद्रीय लोक निर्माण विभाग की विशिष्टियों के अनुरूप कार्य सम्पादित करना होगा तथा बिल के साथ आवश्यक टेस्ट रिपोर्ट जमा किया जाना होगा।
17. कार्य के दौरान होने वाली किसी भी प्रकार की क्षति के लिए विश्वविद्यालय का उत्तरदायित्व अथवा देनदारी नहीं होगी और न ही इस प्रकार का कोई दावा न तो कायदेश प्राप्त निविदाकर्ता द्वारा और न श्रमिकों द्वारा किया जायेगा और न ही विश्वविद्यालय द्वारा स्वीकार किया जायेगा।
18. वित्तीय निविदा में विभिन्न आइटमों की दर्शायी गयी मात्रा अनुमानित है। कार्य सम्पादन के समय किसी भी आइटम की मात्रा में संशोधन हो सकता है या कोई कार्य नहीं भी सम्पादित कराये जाने का निर्णय लिया जा सकता है। उक्त हेतु कायदेश प्राप्त निविदाकर्ता का कोई दावा स्वीकार नहीं होगा।
19. कार्य के दौरान यदि विश्वविद्यालय की बिजली का उपयोग किया जाता है तो प्रति यूनिट ₹ 10.00 के अनुसार कायदेश प्राप्त निविदाकर्ता को विश्वविद्यालय के पक्ष में भुगतान करना होगा। कायदेश प्राप्त निविदाकर्ता द्वारा बिजली मीटर का व्यय स्वयं वहन करना होगा तथा विभाग के इलेक्ट्रीशियन के माध्यम से ही बिजली कनेक्शन लेना होगा।
20. निविदा प्रपत्र एवं संलग्न दस्तावेज के प्रत्येक पृष्ठ पर निविदाकारक द्वारा हस्ताक्षर एवं मुहर लगाना अनिवार्य है।
21. वित्तीय निविदा में दरों का अधिलेखन (Overwriting) मान्य नहीं होगा इसलिए वित्तीय निविदा में दरों को बहुत ही ध्यान से और बिना अधिलेखन (Overwriting) के भरा जाए।
22. वित्तीय निविदा में त्रुटिपूर्ण गणना (Wrong Calculation) मान्य नहीं होंगी। किसी भी प्रकार के संदेह की स्थिति में शब्दों में लिखी गई राशि ही मान्य होगी।
23. निविदा को कुलसचिव कार्यालय में रखे Tender Box में डालना होगा।
24. सभी अर्हताएँ निविदा जमा करने से पूर्व या अंतिम तिथि तक पूर्ण करना अनिवार्य है।
25. कार्य पूर्ण होने के उपरान्त विश्वविद्यालय के अभियंताओं एवं परामर्शदाता द्वारा कार्य के सत्यापन एवं बिल की जाँच के उपरान्त ही भुगतान की कार्यवाही संपन्न की जाएगी।
26. निविदा प्रपत्र प्राप्त करने हेतु 'वित्ताधिकारी, म.गां.अं.हिं.वि., वर्धा (महाराष्ट्र)' के नाम से देय ₹ 500/- (रुपया पांच सौ मात्र) का डिमांड ड्राफ्ट परिसर विकास विभाग में जमा कर निविदा प्रपत्र प्राप्त किया जा सकता है। यदि निविदाकारक द्वारा वेबसाइट से निविदा प्रपत्र डाउनलोड कर निविदा जमा की जाती है तो

उक्त निविदा प्रपत्र के साथ 'वित्ताधिकारी, म.गां.अं.हिं.वि., वर्धा (महाराष्ट्र)' के नाम से देय ₹ 500/- का डिमांड ड्राफ्ट जोड़ना अनिवार्य है।

27. निविदा प्राप्त करने वाली फर्म को कायदेशि जारी होने के 05 दिनों के अंदर निविदा की लागत का 05% Performance Security के रूप में 06 माह के लिए धनराशि डी.डी. के माध्यम से 'वित्ताधिकारी, म.गां. अं.हिं.वि., वर्धा (महाराष्ट्र)' के नाम से विश्वविद्यालय में जमा करना अनिवार्य होगा।
28. तकनीकी निविदा में सफल निविदाकारक को ई-मेल/दूरभाष के माध्यम से सूचित किया जाएगा जिससे तकनीकी निविदा में सफल समस्त निविदाकारक 'वित्तीय निविदा' खुलने के समय उपस्थित रह सकें। अतः लिफाफे के ऊपर ईमेल, मोबाइल नम्बर एवं पता अवश्य लिखें।
29. निविदा में किसी भी प्रकार के परिवर्तन/सुधार/संशोधन होने पर उक्त की सूचना मात्र विश्वविद्यालय की वेबसाइट www.hindivishwa.org पर प्रकाशित की जाएगी इसलिए वेबसाइट लगातार देखते रहें।
30. विश्वविद्यालय के पास किसी भी स्तर पर निविदा में निर्धारित जानकारी, शर्तों, प्रक्रिया और प्रोटोकॉल को रद्द करने और जोड़ने का विवेकाधिकार सुरक्षित होगा। इसके खिलाफ निविदाकर्ता का कोई भी दावा स्वीकार्य नहीं होगा।
31. विश्वविद्यालय बिना कोई कारण बताये किसी भी समय निविदा को निरस्त करने का अधिकार अपने पास सुरक्षित रखता है। किसी भी विवाद की दशा में विवादों का क्षेत्राधिकार वर्धा (महाराष्ट्र) ही होगा।

टेंडर भरने वाले का हस्ताक्षर एवं मुहर

UNDERTAKING REGARDING NOT BEING BLACKLISTED

It is hereby certified that, I/we _____ are not blacklisted by any Ministry/ Departments of Central/ State Government, International bodies like United Nations, World Bank or any other organization/ Funding Agencies as on date. The Organization will immediately inform to M.G.A.H.V, Wardha in case of any change in the situation any time here in after.

Place: _____

Date: __/__/__

Name: _____

Designation _____

Seal

(Financial Bid)

Name of work : Construction of Parking shed in front of Dining and Kitchen (North Campus) at MGAHV, Wardha.

Tender No. MGAHV/CD/34/2023-24/12....

Date: 08.08.2023

S. No.	Description	Quantity	Unit	Rate	Total Amount (In figure)	Total Amount (In words)
	Civil Work					
A1	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sum on plan including disposal of excavated earth upto 50 m and lift upto 1.5 m, disposed soil to be levelled and neatly dressed :					
	All kinds of soil	612.00	Sq.m.			
A2	Earth work in excavation by mechanical means (Hydraulic Excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sum on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.					
	All kinds of soil.	81.90	Cu.m.			
A3	Excavation work in foundation trenches or drains not exceeding 1.5 m in width or 10 sum on plan including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50m.					
	Ordinary rock	81.90	Cu.m			
A4	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level :					
	1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size).	58.35	Cu.m			
A5	Providing and laying in position machine batched, machine mixed and machine vibrated design mix cement concrete of specified grade for reinforced cement concrete work including pumping of concrete to site					

S. No.	Description	Quantity	Unit	Rate	Total Amount (In figure)	Total Amount (In words)
	of laying but excluding the cost of centring, shuttering, finishing and reinforcement, including Admixtures in recommended proportions as per IS 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge. M-25 grade reinforced cement concrete by using 410kg. of cement per cum of concrete. All work upto floor V level. All works upto plinth level	12.96	Cu.m			
A6	Centring and shuttering including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns, etc. for mass concrete.	81.10	Sq.m			
A7	20 mm cement plaster of mix : 1:4 (1 cement : 4 coarse sand)	9.90	Sq.m.			
A8	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete. Thermo-Mechanically Treated bars.	1020.50	Kg.			
A9	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	49.20	Cu.m.			
A10	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	148.68	Cu.m.			
A11	Steel work in built up tubular trusses including cutting, hoisting fixing in position and applying a priming coat of approved steel primer, welded and bolted including special shaped washers etc. complete. Hot finished welded type tubes	4156.75	Kg.			
A12	Supply & installation of precast galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm +/- 5% total coated thickness (TCT), Zinc coating 120gsm as per IS: 277 in 240mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester	278.86	Sq.m.			

S. No.	Description	Quantity	Unit	Rate	Total Amount (In figure)	Total Amount (In words)
A13	top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches while transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55mm) with EPDM seal or with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead complete upto any pitch in horizontal/ vertical or curved surfaces excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. Providing and fixing pre-coated galvanised steel sheet roofing accessories 0.50 mm +/- 5% total coated thickness (TCT), Zinc coating 120gsm as per IS: 277 in 240mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws or with polymer coated J or L hooks, bolts and nuts and or G.I. seam bolts and nuts, G.I. plain and bitumen washers complete : Ridges plain (500 - 600mm).					
A14	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	38.20	Rmt.			
A15	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) upto plinth level with : Cement mortar 1:6 (1 cement : 6 coarse sand)	133.40	Sq.m.			
A16	Random rubble masonry with hard stone in superstructure above plinth level and upto floor five level, including leveling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) at window sills, ceiling level and the like. Cement mortar 1:6 (1 cement : 6 coarse sand)	90.00	Cu.m			
A17	Pointing on stone work with cement mortar 1:3 (1 cement : 3 fine sand) : Raised and cut pointing	8.10	Cu.m			
A18	Providing and fixing on wall face Unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A including jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion. (i) Single socketed pipes	36.00	Sq.m			

S. No.	Description	Quantity	Unit	Rate	Total Amount (In figure)	Total Amount (In words)
	110 mm diameter	3.00	Rmt			
A19	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets etc. upto floor five level, excluding the cost of centring, shuttering and finishing :					
	1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	1.35	Cu.m			
A20	Centring and shuttering including strutting, propping etc. and removal of form for :					
	Small lintels not exceeding 1.5m clear span, moulding as in cornices, window sills, string courses, bands, copings, bed plates, anchor blocks and the like.	6.00	Sq.m			
	Total					
	GST					
	G. Total					

टेंडर भरने वाले का हस्ताक्षर एवं मुहर